

P.O. Box 392, Hinesburg, VT 05461, (802) 238-3478, newleafdesign@gmavt.net

Copyright © 2020, New Leaf Design, LLC

Use without permission is a violation of copyright.


**BUILDING PERFORMANCE PROFESSIONALS ASSOCIATION** 


# **Summary & Report**

**Zero Energy Now Program** 

Contractor/Coordinator	Integrated Solar Applications / New Leaf Design
House Style	Expanded Reproduction Colonial Farmhouse
Location	Windham County, Vermont
Project Start Date	9/25/2019

# How does your home stack up on the path to Zero Energy?





Your home's potential energy profile...

# **Proposed Work Scope**

# Heat Loss Analysis & Envelope Improvement

Envelope Components	Existing Heat Loss in MMBtus	Proposed Reduction	Improved Heat Loss	Cost of Improvement
Flat Attic - Air seal & Insulate				
Attic Slants & Cathedral Ceilings				
Exterior Walls				
Exposed Floors				
Basement A&I				
Basement Moisture				
Special Detail #1				
Special Detail #2				
Special Detail #3				
Living Space Measures				
Envelope Air Flow Analysis	Existing Air Infiltration	Impro	ved Air	
Air Infiltration - CFM50				
Natural Air Changes per Hour				
Mechanical Ventilation				
Envelope Totals				Total Cost
Total Estimated Building Heat Loss	173.60	60.76	112.84	
	Total Cost of Envel	ope Impro	vement	\$ 73,601.00

## **Mechanical Installations**

### **Existing Mechanical Systems**

Mechanical U System Type	nit &	Fuel	Make	Model	Efficiency	Effcy based on
Hydronic Boil	er	#2 Fuel Oil			80.00%	Default
DHW 1	Tank Indired	#2 Fuel Oil			73.60%	Default
DHW 2						

# **Renewable Energy Installations**

Renewable Equipmen	nt - Existing			
		Productn	Annual	

System Type	Size in kW DC	Productn Factor	Annual kWh AC	Other Relevant Details	Extg Rnwbl Input in kWh	Extg Load in kWh
					0.00	4,596.78



### Improved Mechanical Systems

						Effcy based
Mechanical	Unit & System Type	Fuel	Make	Model	Efficiency	on
	Mini-Split ASHP	Electric			220.0%	Default
	Hydronic Boiler	#2 Fuel Oil			80.0%	Default
DHW 1	Heat Pump	Electric	Stiebel Eltron	80 Gallon	200.0%	Default
DHW 2						
				Total Cost of Mechanical Imp	rovement	\$ 33.435.00


Renewable Equipment	- Improved					
System Type	Size in kW DC	Production Factor	Annual kWh AC	Other Relevant Details	Totl Rnwbl Input in kWh	Improved Load in kWh
Roof Mount	10.40	1.20	12,480.00			
					12,480.00	22,027.62
				Total Cost of Renewab	le Installation	\$ 36,768.00

Project Cost	
Weatherization	\$ 73,601.00
Heat Pumps & Appliances	\$ 33,435.00
Biomass Installation	\$ -
Renwble Electric Installation or Buy-In	\$ 36,768.00
Financing Costs	\$ -
Total Project Cost	\$ 143,804.00

Financing & Cash Flow	Ana	alysis
Pre-project Monthly Energy Loan Pymt	\$	-
Pre-Project Monthly Energy Costs	\$	520.35
Pre-Project Monthly Out of Pocket	\$	520.35
Total Project Cost	\$	143,804.00
Total Cash & Rebate Incentives	\$	20,359.68
Down Payment or Cost Offset	\$	123,444.32
Financed Principal	\$	-
Total Monthly Loan Payments	\$	-
Post-Project Monthly Energy Costs	\$	197.31
Annual Energy Savings	\$	3,876.47
Monthly Energy Savings	\$	323.04
Post-Project Monthly Out of Pocket	\$	197.31
Net Monthly Savings	\$	323.04

Incentive	e						
C		(	Cash Back		Tax		Cost
Summar	У	Incentive		Credit		R	eduction
ZEN Incentiv	res						
Test	2 Incentive	\$	5,000.00				
Test	3 Incentive	\$	-				
Inc	ome Bonus	\$	-	\$	-	\$	-
Other Incent	tives						
Wea	therization	\$	1,000.00	\$	-	\$	-
	Mechanical	\$	600.00	\$	300.00	\$	1,800.00
	Renewable	\$	-	\$	9,559.68	\$	-
	Appliance	\$	-	\$	-	\$	-
	Utility	\$	2,400.00	\$	-	\$	-
	Other Adjustmer	\$	-	\$	1,500.00	\$	-
Total							
Incentive	\$ 22,159.68	\$	9,000.00	\$	11,359.68	\$	1,800.00

Financing		Amount to b	\$ -	
	Principal	Term in Years	Rate	Monthly Payment
Loan 1	\$ -			
Loan 2				
Loan 3				
Total Loans	\$ -	Total Month	nly Payment	\$0.00



	Required Standards	Minimum Required	Projected Achievmnt	Meets ZEN
Test 1	Envelope Load Reduction	10.00%	35.00%	YES
Test 2	Fossil & Grid Energy Reduction	50.00%	82.85%	YES
Test 3	Renewable Energy Component	50.00%	50.36%	YES
	Added Benefits	Recmnded	Projected	
	Reduction in CO2 Emissions	90.00%	94.19%	lbs elimntd: 37,036.41
	Energy Cost Savings	80.00%	68.96%	in pre-project dollars

Project Design	Primary Fossil Fuel	Load In Mmbtus			Likely Difference in	
Optimization	#2 Fuel Oil	9.40	In Native Units	In Dollars	Project Cost	Apply
Adjst Env Load MMBtus						
Adjust HP Load MMBtus						
Adjust PV Output kWh						
Install HP DHW						
Other FF Appliance Chnge:						
Adjust Biomass Use						
Adjst cost of Fuel						
Fossil Fuel (Consmptn)	Primary Fuel Cost	HP Load	kWh Load	Monthly OP	Net Project Cost	Sav/Mo
112.84 11.75	\$ 2.97	103.44	22,027.62	\$ 197.31	\$ 123,444.32	\$ 323.04

### Windham County Colonial Reproduction -- original house built in 1972

A very large project that was admitted to the program after it was completed because it involved all three major ZEN components, and met the requirements for entry and all the standards. The house had had an enormous pre-project heating load – 173 million Btus, and an enormous weatherization project was undertaken to address it – over \$73,000. We gave it a nominal 35% envelope improvement which allowed the 10.4 kW solar array to cover over 50% of the energy load. We expect the home to perform at much higher levels, and look forward to verifying the results after a few years. This project was self-financed.